OFFICE OF THE SUPERINTENDENT, GOVERNMENT GARDENS IN MYSORE, LAL-BAGH, BANGALORE.

Dated 28th July 1933.

Notice is hereby given that separate sealed tenders will be received at the Office of the Superintendent, Government Gardens in Mysore, Lal-Bagh, Bangalore, up to 4 P.M. on 15th August 1933 for A. annual repairs and special works to be done to buildings, culverts, etc., B. special repairs to roads, C. earth work in Lal-Bagh, Cubbon Park, etc., up to the end of June 1934.

2. Tenders should be submitted on printed forms (which may be obtained from the office of the undersigned) showing the rates at which different items specified will be executed

3. Each tender must be accompanied by a deposit of rupees one hundred in cash as earnest money and it should be superscribed "Tender for Annual Repairs and Special Works of Buildings, Culverts, etc.," "Special Repairs to Roads," "Earth Work," in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Superintendent, Government Gardens in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatsoever for the rejection of any tender.

5. Within eight days of the acceptance of the tender, the successful competitior will be required to execute the usual contract bond, in default of which his tender will be cancelled and his earnest money will be forfeited to Government.

6. The successful competitor whose tender is accepted will be informed in due course. No enquiries regarding the acceptance or rejection of tender will receive any reply.

7. The earnest money on rejected tenders will be returned.

8. Rate should be quoted for each item of work.

9. Percentage rates either below the estimated amount or the lowest tender will not be accepted.

10. In case of the non-tendered item, the departmental rates should be accepted by the contractor.

11. The undersigned reserves the right to get any work executed by departmental agency.

12. No claims for enhanced rates should be preferred at any time during the period of contract.

13. In all matters of dispute regarding quantity of work or rates, etc., the decision of the Superintendent, Government Gardens in Mysore, is final.

14. After completion of each estimated work, final measurements will be taken and checked, and the bill concerned will be arranged for payment.

Sl. No.	Items	Per	Rate to be given
	A. BUILDINGS—Annual Repairs and Special Works.		
1	Earth work excavation for foundation and filling in basement with consolidation :—		
	(a) Ordinary red or black soil	C.yd.	
	(b) Gravelly hard soil	"	
2	Building foundation burnt stone in mud	C.ft.	
3	Do stone in mortar	"	
4	Basement burnt stone in mud	"	
5	Do in mortar	"	
6	Walls stone in mud	"	
7	Do mortar	"	
8	Do burnt brick in mud	"	
9	Do do in mortar	"	
10	Arch work burnt brick in mud including centering ..	"	
11	Do mortar including centering ...	"	
12	Burnt stone dry wall and rivetment	"	
13	Mud wall	"	
14	Burnt stone slabs 5" to 6" thick roughly dressed including cement pointing.	Sq.ft.	
15	Do with one line dressing including cement pointing.	"	
16	Do with two lines dressing including cement pointing.	"	
17	Removing and refixing old stone slabs with one line dressing for steps, etc.	"	

Sl. No.	Items	Per	Rate to be given
19	Stone slab pillars with grooves cut	Sq. ft.	
20	Plastering with mortar stone wall	Square	
21	(a) Do brick wall	,,	
	(b) Do (rough plastering)	,,	
22	Plastering with cement stone wall	,,	
23	Do brick wall	,,	
24	Plastering with clay	,,	
25	Pointing with mortar	,,	
26	Pointing with cement	,,	
27	Whitewashing two coats, including petty repairs ..	,,	
27a	Colour washing two coats after petty repairs including a coat of white washing.	,,	
28	Building coping for a wall of 9" thick including chunam plastering.	R. ft.	
29	Repairs to coping and patty	,,	
30	Repairs to caps of pilasters in compound wall ...	Each	
31	Painting two coats of deep green or chacolate or silver gray or signar red paint after cleaning the old paint to doors, windows, etc.	Square	
32	Painting white lead to doors, windows, etc., two coats after cleaning the old paint.	,,	
33	Painting two coats of aluminium paint after cleaning the old paint.	,,	
34	Wood oiling two coats	,,	
35	Removing broken chunam plastering and cement plastering the ornamental parapet walls of culverts and steps	R.ft.	
36	Repairing the ornamental parapet wall of Balastrades with chunam.	,,	
37	Cement washing two coats including petty repairs ...	Square	
38	Distemper washing two coats including petty repairs ...	,,	
39	Calcarium washing two coats including petty repairs ...	,,	
40	Renewing glass panes 1/8" thick	Sq. ft.	
41	Roofing with first class Mangalore tiles with teek reapers ..	Square	
41a	Pucca terrace roofing complete	,,	
42	Jack arch roofing complete	,,	
43	Roofing with re-inforced concrete complete ...	,,	
44	Roofing with 1½" thick cuddapah slabs complete ..	,,	
45	(a) Removing old Mangalore tiled roof and refixing ...	,,	
	(b) Teakwood wrought and put up	C. ft.	
	(c) Jungle wood wrought and put up	,,	
46	(a) Renewing 1/8" thick glasses for roof with clearing the grooves allowing air space.	Sq. ft.	
	(b) Providing wire netting with iron stays and teak reapers complete above glass roof.	,,	
47	Providing expanded metal pannels with teak wood frame to the open spaces between stone posts and fixing with iron clamps.	,,	
47a	Providing expanded metal partition with teak wood frames with a double door way in the centre with fittings.	,,	
48	Flooring with granite slabs 4" thick one line dress over surki concrete 3" thick including cement pointing.	,,	
49	Do over sand bed including cement pointing.	,,	
50	Flooring with cuddapah slabs 1" thick over surki concrete 3" thick including cement pointing.	,,	
51	Teak wood doors with panel shutters	,,	
52	Do with battened shutters	,,	
53	Teakwood windows with iron bars and glazed and panel shutters.	,,	
54	Do with glazed shutters only ..	,,	
55	Do with panel shutters only ..	,,	
56	Providing expanded metal to existing windows of glazed shutters in the frame towards the shutters by deepening the groove	,,	

Sl. No	Items	Per	Rate to be given
61	Tarring to wood or wall	Sq.ft.	
62	Stone pitching (with new stones)	"	
63	Do (with old stones)	"	
64	Curb stones 4" thick, 12" width with top dressed one line and rounded including fixing.	R.ft.	
65	Combined white and colour washing two coats to ornamental parapet walls	"	
66	Renewing roofing Mangalore tiles	Each	
67	Do roofing ridge tiles	"	
68	New cornice work 6" thick	R.ft.	
69	Do 9" do	"	
70	Repairing cornice with mortar 6" thick	"	
71	Do 9" thick	"	
71a	Stone jelly in chunam concrete	C.ft.	
72	Surki concrete	"	
73	Stone jelly in cement concrete	"	
74	Building new ornamental parapet wall with pillar foundations of 2 ft. cube, covered with 6" thick stone slabs of 2 ft. width and the parapet with burnt brick in mortar and the balastrades of cement mould and cement plastering as per design in the Lal-Bagh garden complete.	R.ft.	
75	Do Ornamental parapet as per design in the Terrace garden near big fountain.	"	
	B. ROADS—Special works.		
76	Picking and forming laterite or metal road surface ...	Sq.yd	
77	Spreading and consolidation with heavy stone roller of laterite or metal with gravel and sand.	C.yd.	
78	Watering charges	Sq.ft.	
79	Barricading and night watch	Daily.	
	C. EARTH WORK.		
80	Digging pits, trenches, etc., with a lead of 20 yards ..	C.yd.	—
81	Filling earth for raising surfaces of maidan or roads with a lead of half-mile in Park area.	"	
82	Silt clearing in ponds, channels, etc., and filling the hollows, etc, within a distance of one furlong.	"	
83	Silt cleaing in the chambers of the Septic Tank in the Horticultural Farm including baling out water.	"	

H. C. JAVARAYA,
Superintendent.

MYSORE DISTRICT.

Resale Notification, dated the 15th July 1933.

It is hereby notified for general information that the exclusive right of collecting the Minor Forest Produce, on all Government unoccupied lands, Amrut Mahal Kavals, State Forests, Reserved Lands and Plantations of the undermentioned Taluks from the date of confirmation of sale to 30th June 1934 will be resold at 2 P.M., on the 18th August 1933 by the Deputy Commissioner, Mysore District, in the Deputy Commissioner's Court Hall, Mysore, at the risk of the original purchasers, subject to the conditions specified in the detailed Notification, dated 30th May 1932, since the original purchasers have failed to pay the 2nd khist due on 1st July 1933.

Nanjangud	Periyapatna
Gundlupet	Krishnarajpete
Chamarajnagar	Nagamangala
Hunsur	Seringapatam
Heggaddevankote	